

EXISTING SITE AND DEMOLITION PLAN

SPECIAL BUILDING SET BACK LINE NOTES:

- THE BUILDING OUTLINE SHOWN ON THE PLANS IS ASSUMING THE MOST OUTSIDE PART OF THE BUILDING.
- 2. THE MOST OUTSIDE PART OF THE BUILDING INCLUDES ALL SIDING, SHUTTERS, GUTTERS, DOWNSPOUTS, DOWNSPUT BOOTS, TRIM WORK OF ANY KIND OR TYPE OF COVERING OR AESTETIC PART OF THE BUILDING.
- 3. CONTRACTOR IS TO COORDINATE BUILDING WITH THE OWNER AND ARCHITECT TO MAKE SURE THAT NO PART OF THE BUILDING, WITH THE EXCEPTION OF THE OVERHANG, PROTRUDES OUTSIDE OF THE BUILDING SET BACK LINE VERTICALLY FROM THE GROUND LINE TO THE BOTTOM OF THE ROOF OVERHANG. GUTTER SYSTEM IS TO BE INCLUDED AS PART OF THE ALLOWED OVERHANG.
- 4. CONSULT THE TYBEE PLANNING AND ZONING DEPARTMENT FOR BUILDING SET BACK LINE REQUIREMENTS IF A GUTTER SYSTEM IS UTILIZED AND FOR DOWNSPOUTS, DOWNSPOUT BOOTS, FIREPLACES, ELEVATOR SHAFTS, ROOF DECKS, STAIRS AND AC COMPRESSORS.
- CONSULT THE TYBEE PLANNING AND ZONING DEPARTMENT FOR BUILDING SET BACK LINE REQUIREMENTS IF A SPREAD FOOTING IS USED.
- CERTIFICATE OF OCCUPANCY WILL NOT BE GRANTED IF ANY PART OF THE BUILDING (INCLUDING SIDING, SHUTTERS, GUTTERS, DOWNSPOUTS, DOWNSPOUT BOOTS, TRIM, WATER TABLE OR ANY AESTECTIC WORK, ETC.) EXTENDS OVER THE BUILDING SET BACK LINE WITHOUT A VARIANCE.

TRAFFIC AND RIGHT-OF-WAY NOTES:

INTO THE STORMWATER SYSTEM.

PERSONNEL.

. ALL ROAD CLOSINGS, DETOURS AND ETC. ARE TO BE

COORDINATED WITH THE CITY OF TYBEE ISLAND, GEORGIA

2. ANY AND ALL NECESSARY PERMITS MUST BE OBTAINED FROM THE CITY OF TYBEE ISLAND PRIOR TO COMMENCEMENT

3. CONTRACTOR IS TO OBTAIN A R.O.W. PERMIT PRIOR TO

PERFORMING ANY WORK WITHIN THE CITY OF TYBEE ISLAND

4. CHLORINATED DISINFECTED WATER SHALL NOT BE DISCHARGED

GEORGIA D.O.T. NOTES

I . ANY AND ALL WORK WITHIN ANY GEORGIA D.O.T. RIGHT-OF-WAYS MUST BE APPROVED AND PERMITTED THROUGH THE GEORGIA D.O.T.

SPECIAL F.F. NOTES :

I. CONTRACTOR TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES AND COORDINATE WITH GOVERNING AGENCY REQUIREMENTS. 2. CONTRACTOR TO COORDINATE FINISH FLOOR ELEVATIONS WITH STRUCTURAL, ARCHITECTURAL AND M.E.P. PLANS.

SPECIAL AVERAGE GRADE NOTES:

. THE AVERAGE GRADE TO BE USED AS A BASE ELEVATION TO SET THE BUILDING HEIGHT IS TO BE OBTAINED FROM THE TYBEE ISLAND PLANNING AND ZONING DEPARTMENT.

NOTES:

. CONTRACTOR IS TO COORDINATE ALL GAS, LIGHTING, ELECTRICAL, PHONE, CABLE AND ANY OTHER REQUIRED UTILITIES WITH THE APPROPRIATE UTILITY AGENCIES.

2. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO COMMENCING OF CONSTRUCTION ACTIVITIES AND FOR AVOIDING CONFLICT WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.

3. CONTRACTOR IS TO COORDINATE ALL DEMOLITION WORK WITH THE OWNER. ALL ITEMS NOT TO BE RELOCATED OR GIVEN TO THE OWNER WILL BECOME THE PROPERTY OF THE CONTRACTOR.

4. REMOVE ALL TREES AS NECESSARY FOR PROPOSED CONSTRUCTION.

X TREES TO BE REMOVED

BUILDINGS IN "AE" ZONES ARE TO HAVE THE FINISHED FLOOR SET A MINIMUM OF 1' ABOVE FLOOD.

PECIAL AE AND VE ZONE NOTES


2. BUILDINGS IN "VE" ZONES ARE TO HAVE THE LOWEST HORIZONTAL STRUCTURAL MEMBER SET A MINIMUM OF 1' ABOVE FLOOD.

3. BUILDINGS IN AE AND VE ZONES ARE TO HAVE ALL ELECTRICAL. PLUMBING. HVAC, DUCTWORK AND OTHER EQUIPMENT TO BE A MINIMUM OF 1' ABOVE

4. FLOOD VENTS ARE REQUIRED IN "AE" ZONES AND ARE TO HAVE I SQUARE INCH / SQUARE FOOT OF ENCLOSED AREA WITH A MINIMUM ROUND OPENING OF 3", A MINIMUM OF 2 OPENINGS WITH ALL OPENINGS EVENLY SPACED AROUND PERIMETER. BOTTOM OF OPENING SHALL BE 12" OR LESS ABOVE

5. BREAK AWAY WALLS ARE REQUIRED IN "VE" ZONES.

6. COORDINATE SITE WORK AND FINISHED FLOOR ELEVATIONS WITH ARCHITECTURAL PLANS TO MAKE SURE BUILDING ELEVATIONS ARE SET AS PER



LEGEND NEW EXISTING DESCRIPTION

BUILDING RESURFACE ASPHALT PAVEMENT

ASPHALT PAVEMENT TYPE I

SANITARY SEWER LINE

ASPHALT PAVEMENT TYPE I

CONCRETE PAVEMENT

CONCRETE SIDEWALK

STORM DRAIN LINE

WATER LINE

SANITARY SEWER MANHOLE

GAS VALVE

WATER METER

WATER VALVE

FIRE HYDRANT

FLARED END SECTION

CONTOUR

CHAIN LINK FENCE

IRON PIN FOUND

TOP OF GUTTER

SPOT ELEVATION **9** _9⁻ \

I.E.4.13 I.E.4.13 INVERT ELEVATION

DITCH INVERT

PROPERTY LINE

TW 16.83 TOP OF WALK

TP 14.65

TG 16.10

TOP OF PAVEMENT FG 16.1 FINISHED GRADE TS 16.10 TOP OF STONE

TC 16.10 TOP OF CURB

Project Information:

P.I.N.: 40005-20009

PROJECT ADDRESS: No. 5, 7th Street TYBEE ISLAND, GEORGIA 31328

ZONING: R2

SITE SIZE : 0.65 ACRES (TOTAL)

ESTIMATED DISTURBED AREA: 0.15 ACRES DEVELOPER: CABRETTA CAPITAL

BRENT WATTS 49 PARK OF COMMERCE WAY SAVANNAH, GEORGIA 31405


PHONE: 404-307-2868

FEMA MAP NOTES:

. THIS DEVELOPMENT IS WITHIN FLOOD ZONE "AE-9" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 13051C -, MAP REVISED --(88 DATUM).


2. CONTRACTOR IS TO VERIFY FEMA ELEVATIONS PRIOR TO Y CONSTRUCTION ACTIVITIES.

Survey: BREWER SURVEYING Date of Survey : JULY, 2023 Datum : NAVD 88



SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABALY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.







Drawing Number

PROPOSED SITE PLAN

GENERAL BUILDING INFORMATION NOTES:

OUTSIDE PART OF THE BUILDING.

2. OUTFALL FOR THE PROJECT WILL BE DICTATED BY EXISTING CONDITIONS WITHIN THE

. PROPOSED BUILDING FINISHED FLOOR ELEVATIONS ARE TO BE SET AS PER FEMA FLOOD STUDY MAPS AND AS PER THE CITY OF TYBEE ISLAND, GEORGIA ORDINANCES

2. PROPOSED BUILDINGS ARE TO BE SUPPORTED ON PIERS OR FOUNDATIONS WHICH WILL SATISFY FEMA ELEVATION AND FEMA ZONE REQUIREMENTS AS WELL AS TYBEE ISLAND REQUIREMENTS.

EXISTING PROPOSED TOPO CONTOURS -----DRAINAGE FLOW ARROWS TOP OF PARKING

TRAFFIC AND RIGHT-OF-WAY NOTES:

ALL ROAD CLOSINGS, DETOURS AND ETC. ARE TO BE COORDINATED WITH THE CITY OF TYBEE ISLAND, GEORGIA PERSONNEL.

2. ANY AND ALL NECESSARY PERMITS MUST BE OBTAINED FROM THE CITY OF TYBEE ISLAND PRIOR TO COMMENCEMENT OF ANY WORK WITHIN RIGHT-OF-WAY.

THE OWNER, ENGINEER AND SURVEYOR ARE TO COORDINATE ALL EASEMENTS PRIOR TO FINAL PLAT APPROVAL AND

. ALL DRAINAGE EASEMENTS TO BE PRIVATELY MAINTAINED.

SPECIAL BUILDING SET BACK LINE NOTES: THE BUILDING OUTLINE SHOWN ON THE PLANS IS ASSUMING THE MOST

. THE MOST OUTSIDE PART OF THE BUILDING INCLUDES ALL SIDING, SHUTTERS, GUTTERS, DOWNSPOUTS, DOWNSPUT BOOTS, TRIM WORK OF

ANY KIND OR TYPE OF COVERING OR AESTETIC PART OF THE BUILDING.

CONTRACTOR IS TO COORDINATE BUILDING WITH THE OWNER AND ARCHITECT TO MAKE SURE THAT NO PART OF THE BUILDING, WITH THE EXCEPTION OF THE OVERHANG, PROTRUDES OUTSIDE OF THE BUILDING SET BACK LINE VERTICALLY FROM THE GROUND LINE TO THE BOTTOM OF THE ROOF OVERHANG. GUTTER SYSTEM IS TO BE INCLUDED AS PART OF THE ALLOWED OVERHANG.

. CONSULT THE TYBEE PLANNING AND ZONING DEPARTMENT FOR BUILDING SET BACK LINE REQUIREMENTS IF A GUTTER SYSTEM IS UTILIZED AND FOR DOWNSPOUTS, DOWNSPOUT BOOTS, FIREPLACES, ELEVATOR SHAFTS, ROOF DECKS, STAIRS AND AC COMPRESSORS.

CONSULT THE TYBEE PLANNING AND ZONING DEPARTMENT FOR BUILDING SET BACK LINE REQUIREMENTS IF A SPREAD FOOTING IS USED.

CERTIFICATE OF OCCUPANCY WILL NOT BE GRANTED IF ANY PART OF THE BUILDING (INCLUDING SIDING, SHUTTERS, GUTTERS, DOWNSPOUTS, DOWNSPOUT BOOTS, TRIM, WATER TABLE OR ANY AESTECTIC WORK, ETC.) EXTENDS OVER THE BUILDING SET BACK LINE WITHOUT A VARIANCE.

TOTAL AREA TRAFFIC RATED PERMEABLE PAVERS MIN. 3-1/8" THICK WITH TYP. NO. 89 STONE IN OPENINGS - 6" (MIN.) WIDE X 12" (MIN.) DEEP 1.5" TO 2" OF NO. 89 STONE ---FLUSH CONCRETE HEADER CURB BEDDING COURSE 4" OF NO. 57 STONE OPEN-GRADED BASE 10" OF NO. 2, 3 OR 4 STONE SUB -BASE TYPE AND INSTALLATION TO BE AS PER MANUF. SPECIFICATIONS EXISTING UNDISTERBED SOIL -SPECIAL INSTALLATION NOTE: ALL INSTALLATION PROCEDURES AND MATERIALS SHALL BE AS PER THE

PAVER MANUFACTURER INSTRUCTIONS AND RECOMMENDATIONS.

8% TO 10% OF ---

I. ALL CONSTRUCTION SHALL CONFORM TO THE APPLICABLE CITY OF TYBEE ISLAND DEVELOPMENT GUIDELINES, TECHNICAL SPECIFICATIONS AND STANDARD DETAILS.

2. CONCRETE TO BE 3,000 PSI AND REINFORCED WITH FIBERMESH OR STEEL.

3. CONCRETE HEADER CURB DIMENSIONS MAY DIFFER BASED ON PROJECT SPECIFIC DESIGN REQUIREMENTS.


4. BASE COMPACTION UNDER CURB TO BE 98% (ASTM D698).

5. CONTRACTION JOINTS TO BE SAW CUT NO LATER THAN 24 HOURS AFTER THE POUR.


6. SYSTEM IS TO BE APPROVED BY TYBEE ISLAND PRIOR TO INSTALLATION.


PERMEABLE PAVER DETAIL (25 YEAR PAVER)


NOT TO SCALE



ROOF PLAN







Special Pre-Construction Note: Contractor to verify all existing and proposed structure locations (drainage, sanitary, etc.), tops and depths prior to ordering materials or beginning construction.

FEMA MAP NOTES :

1. THIS DEVELOPMENT IS WITHIN FLOOD ZONE "AE-9" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 13051C -, MAP REVISED --(88 DATUM).

2. CONTRACTOR IS TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES.

Survey Information : Survey: BREWER SURVEYIN Date of Survey : JULY, 202 Datum : NAVD 88

TO ENSURE THAT ALL ROOF RUN-OFF IS DIRECTED TO THE TYBEE ISLAND

BUILDING DESIGNER SHALL SIZE GUTTER SYSTEM TO CONVEY A 25 YEAR (MIN) STORM EVENT (8" PER HOUR).

NOT BE ALLOWED TO IMPACT ADJACENT PROPERTIES.

REQUIREMENTS OF GUTTERS, DOWNSPOUTS AND DOWNSPOUT BOOTS AND HOW BUILDING SET BACK LINES ARE IMPACTED BY THE GUTTER AND DOWNSPOUT SYSTEM PRIOR TO CONSTRUCTION.

CONTRACTOR.

I. CONTRACTOR IS TO COORDINATE ALL GAS, LIGHTING, ELECTRICAL PHONE, CABLE AND ANY OTHER REQUIRED UTILITIES WITH THE APPROPRIATE UTILITY AGENCIES.

2. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO COMMENCING OF CONSTRUCTION ACTIVITIES AND FOR AVOIDING CONFLICT WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE

3. CONTRACTOR IS TO COORDINATE ALL DEMOLITION WORK WITH THE OWNER. ALL ITEMS NOT TO BE RELOCATED OR GIVEN TO THE

5. REMOVE ALL TREES AS NECESSARY FOR PROPOSED

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.



No. 28372 PROFESSIONAL

PRIOR TO DIGGING

Drawing Number

2 OF 7 SHEETS

SPECIAL AVERAGE GRADE NOTES:

BUILDINGS IN "AE" ZONES ARE TO HAVE THE FINISHED FLOOR SET A

. BUILDINGS IN "VE" ZONES ARE TO HAVE THE LOWEST HORIZONTAL

. BUILDINGS IN AE AND VE ZONES ARE TO HAVE ALL ELECTRICAL, PLUMBING,

VAC, DUCTWORK AND OTHER EQUIPMENT TO BE A MINIMUM OF 1' ABOVE

. FLOOD VENTS ARE REQUIRED IN "AE" ZONES AND ARE TO HAVE I SQUARE

INCH / SQUARE FOOT OF ENCLOSED AREA WITH A MINIMUM ROUND OPENING

RCHITECTURAL PLANS TO MAKE SURE BUILDING ELEVATIONS ARE SET AS PER

OF 3", A MINIMUM OF 2 OPENINGS WITH ALL OPENINGS EVENLY SPACED

COORDINATE SITE WORK AND FINISHED FLOOR ELEVATIONS WITH

AROUND PERIMETER. BOTTOM OF OPENING SHALL BE 12" OR LESS ABOVE

STRUCTURAL MEMBER SET A MINIMUM OF 1' ABOVE FLOOD.

. BREAK AWAY WALLS ARE REQUIRED IN "VE" ZONES.

INIMUM OF I' ABOVE FLOOD.

THE AVERAGE GRADE TO BE USED AS A BASE ELEVATION TO SET THE BUILDING HEIGHT IS TO BE OBTAINED FROM THE TYBEE ISLAND PLANNING AND ZONING DEPARTMENT.

THE SITE WILL NEED TO BE GRADED AS SHOWN AND AS DICTATED BY EXISTING CONDITIONS WHICH CAN NOT BE FORSEEN TO ALLOW FOR PROPER DRAINAGE.

SPECIAL BUILDING GUTTER NOTES:

GENERAL DRAINAGE NOTES:

A BUILDING GUTTER SYSTEM AS SHOWN ON THE PLANS SHALL BE UTILIZED RIGHT OF WAY.

CITY OF TYBEE EXISTING DRAINAGE SYSTEM AND EASEMENTS.

. INCREASED STORM WATER RUN-OFF DUE TO NEW IMPERVIOUS AREAS WILL

. CONSULT TYBEE ISLAND PLANNING AND ZONING DEPARTMENT REGARDING

OWNER WILL BECOME THE PROPERTY OF THE CONTRACTOR.

4. REMOVE ALL UNDERGROUND UTILITIES NOT TO BE UTILIZED. DO NOT ABANDON UTILITIES IN PLACE.

6. PREVENT DAMAGE TO EXISTING TREES WHERE POSSIBLE.

X TREES TO BE REMOVED.

SOIL EROSION AND SEDIMENT CONTROL PLAN - PHASE I

WETLANDS NOTE:

ALL WETLANDS ARE UNDER JURISDICTION OF THE CORPS OF ENGINEERS AND/OR STATE OF GEORGIA DEPARTMENT OF NATURAL RESOURCES. LOT OWNERS AND THE DEVELOPER ARE SUBJECT TO PENALTY BY LAW FOR DISTURBANCE TO THESE PROTECTED AREAS WITHOUT PROPER PERMIT APPLICATIONS AND APPROVAL.

STREAM BUFFER ENCROACHMENT NOTES:

- 1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCROACH IN THE 25 OR 50 FOOT STREAM BUFFER.
- 2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT STREAM BUFFER AS MEASURED FROM THE POINT OF WRESTED VEGETATION WITHOUT FIRST OBTAINING THE NECESSARY VARIANCES AND PERMITS.

BMP REMOVAL NOTE :

1. RETROFITS, PERIMETER SILT FENCE
AND CONSTRUCTION EXIT TO BE LEFT IN PLACE
UNTIL FINAL STABILIZATION
HAS OCCURED.

LEVEL II CERTIFICATION NO. 2104 ISSUED 11-5-05 EXPIRES 11-5-23 SOIL EROSION LEGEND

NON SENSITIVE TYPE SEDIMENT BARRIER

Sd1-I

SENSITIVE TYPE SEDIMENT BARRIER

Sd1-

MPORARY HAY BALES

301-nb)

MULCHING

CONSTRUCTION EXIT

Ds1
Ds2

ITH TEMPORARY SEEDING

Ds3

DISTURBED AREA STABILIZATION WITH SODDING

Ds4

Cd-S

STORM DRAINAGE OUTLET PROTECTION

St

INLET SEDIMENT TRAP
SEDIMENT TRAP

Sd2 Sd3

CHANNEL STABILIZATION
VEGATATION
ROCK RIP—RAP
CONCRETE

LEVEL SPREADER

GEOTEXTILE

Lv

RETROFIT

FLOATING SURFACE SKIMMER

Rt

Ch

DUST CONTROL

Du Sk

FEMA MAP NOTES :

1. THIS DEVELOPMENT IS WITHIN FLOOD ZONE "AE-9" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 13051C -, MAP REVISED --

2. CONTRACTOR IS TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES.

Survey Information :

Survey: BREWER SURVEYING

Date of Survey: JULY, 2023

Datum: NAVD 88

Erosion and Sediment Control Phasing

Initial Phase (Phase I)

1. This phase shall include Silt fencing and construction exits and sediment and detention ponds to be installed prior to any land disturbing

activities to prevent sediment from leaving the site.

Intermediate Phase (Phase II)

1. This phase shall include construction of any outlet structures, retrofits, check dams, inlets protection and temporary grassing.

Final Phase (Phase III)

1. This phase shall include outfall protection, any revised inlet protection and any other permanent devices.

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY
BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT
IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO
REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED
TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK
REQUIRED TO BE RE—CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY
OR CONFLICT.

SCALE: I" = 20'
20'
40' 5

REVISIONS

ESIGN SERVICES, IN 4700 EAST HIGHWAY 80 Unit N, Suite 1 3:103 NASSAU DRIVE NAH, GEORGIA 31410

SOSWELL DESI OFFICE: 47001 Unit MAILING: 10 SAVANNAH 912 -



ATE : JANUARY 26, 2024

OB NO. ---

DATE : JA

No. 5, 7th Street
EE ISLAND, GEORGIA 31328
FOR
CABRETTA CAPITOL
SAVANNAH, GFORGIA

NO. 5, 7TH S
TYBEE ISLAND, GEC
FOR
CABRETTA C
SAVANNAH, G





Drawing Number

SOIL EROSION AND SEDIMENT CONTROL PLAN - PHASE II

SOIL EROSION LEGEND NON SENSITIVE TYPE SEDIMENT BARRIER SENSITIVE TYPE SEDIMENT BARRIER TEMPORARY HAY BALES CONSTRUCTION EXIT MULCHING CHECK DAM STORM DRAINAGE OUTLET PROTECTION Sd2 INLET SEDIMENT TRAP SEDIMENT TRAP Ge GEOTEXTILE CHANNEL STABILIZATION
VEGATATION
ROCK RIP—RAP
CONCRETE LEVEL SPREADER RETROFIT DUST CONTROL FLOATING SURFACE SKIMMER

FEMA MAP NOTES :

1. THIS DEVELOPMENT IS WITHIN FLOOD ZONE "AE-9" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 13051C -, MAP REVISED --

2. CONTRACTOR IS TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES.

Survey Information .

Survey : BREWER SURVEYING Date of Survey: JULY, 2023 Datum : NAVD 88

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY
BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT
IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO
REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED
TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK
REQUIRED TO BE RE—CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY
OR CONFLICT.

Initial Phase (Phase I)

WETLANDS NOTE:

Erosion and Sediment Control Phasing

1. This phase shall include Silt fencing and construction exits and sediment and detention ponds to be installed prior to any land disturbing activities to prevent sediment from leaving the site.

ALL WETLANDS ARE UNDER JURISDICTION OF THE CORPS OF ENGINEERS AND/OR STATE OF GEORGIA DEPARTMENT OF NATURAL RESOURCES. LOT OWNERS AND THE DEVELOPER ARE SUBJECT TO PENALTY BY LAW FOR DISTURBANCE TO THESE PROTECTED AREAS WITHOUT PROPER PERMIT APPLICATIONS AND APPROVAL.

Intermediate Phase (Phase II)

1. This phase shall include construction of any outlet structures, retrofits, check dams, inlets protection and temporary grassing.

Final Phase (Phase III)

1. This phase shall include outfall protection, any revised inlet protection and any other permanent devices.

1. RETROFITS, PERIMETER SILT FENCE
AND CONSTRUCTION EXIT TO BE LEFT IN PLACE
UNTIL FINAL STABILIZATION

BMP REMOVAL NOTE:

HAS OCCURED.

LEVEL II CERTIFICATION NO. 2104 ISSUED 11-5-05 EXPIRES 11-5-23

Cd-S)

PRIOR TO DIGGING



DRAWING NUMBER

4 OF 7 SHEETS

STREAM BUFFER ENCROACHMENT NOTES:

1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCROACH IN THE 25 OR 50 FOOT STREAM BUFFER.

2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT STREAM BUFFER AS MEASURED FROM THE POINT OF WRESTED VEGETATION WITHOUT FIRST OBTAINING THE NECESSARY VARIANCES AND PERMITS.

SOIL EROSION AND SEDIMENT CONTROL PLAN - PHASE III

FEMA MAP NOTES:

1. THIS DEVELOPMENT IS WITHIN FLOOD ZONE "AE-9" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 13051C -, MAP REVISED --

2. CONTRACTOR IS TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES.

Survey Information : Survey : BREWER SURVEYING

Date of Survey : JULY, 2023 Datum : NAVD 88

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY
BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT
IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO
REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED
TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK
REQUIRED TO BE RE—CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY
OR CONFLICT.

WETLANDS NOTE:

ALL WETLANDS ARE UNDER JURISDICTION OF THE CORPS OF ENGINEERS AND/OR STATE OF GEORGIA DEPARTMENT OF NATURAL RESOURCES. LOT OWNERS AND THE DEVELOPER ARE SUBJECT TO PENALTY BY LAW FOR DISTURBANCE TO THESE PROTECTED AREAS WITHOUT PROPER PERMIT APPLICATIONS AND APPROVAL.

SOIL EROSION LEGEND

NON SENSITIVE TYPE SEDIMENT BARRIER

SENSITIVE TYPE SEDIMENT BARRIER

Ds1

Ds4

(Cd-S)

St

Sd2

Sd3

Ge

Ch

Lv

Rt

Ds2 Ds3

STORM DRAINAGE OUTLET PROTECTION

INLET SEDIMENT TRAP

GEOTEXTILE CHANNEL STABILIZATION VEGATATION ROCK RIP—RAP CONCRETE

LEVEL SPREADER

DUST CONTROL

FLOATING SURFACE SKIMMER

Du

Sk

STREAM BUFFER ENCROACHMENT NOTES:

- 1. NEW STRUCTURES ON THIS PROJECT DO NOT ENCROACH IN THE 25 OR 50 FOOT STREAM
- 2. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50 FOOT STREAM BUFFER AS MEASURED FROM THE POINT OF WRESTED VEGETATION WITHOUT FIRST OBTAINING THE NECESSARY VARIANCES AND PERMITS.

Erosion and Sediment Control Phasing

Initial Phase (Phase I)

1. This phase shall include Silt fencing and construction exits and sediment and detention ponds to be installed prior to any land disturbing activities to prevent sediment from leaving the site.

Intermediate Phase (Phase II)

1. This phase shall include construction of any outlet structures, retrofits, check dams, inlets protection and temporary grassing.


Final Phase (Phase III)

1. This phase shall include outfall protection, any revised inlet protection and any other permanent devices.

BMP REMOVAL NOTE :

1. RETROFITS, PERIMETER SILT FENCE
AND CONSTRUCTION EXIT TO BE LEFT IN PLACE
UNTIL FINAL STABILIZATION
HAS OCCURED.

LEVEL II CERTIFICATION NO. 2104 ISSUED 11-5-05 EXPIRES 11-5-23



PRIOR TO DIGGING

No. 28372
PROFESSIONAL
1-26-24 1-26-24 MARY A. BOSWE

DRAWING NUMBER

SOIL EROSION & SEDIMENTATION CONTROL NOTES

1. NARRATIVE: THE EXISTING SITE CONTAINS AN EXISTING RESIDENTIAL STRUCTURE AND THE GROUND IS GENERALLY FLAT WITH SLOPES BETWEEN 0 PERCENT AND 2 PERCENT WITH FEW TREES. THE PROPOSED PROJECT WILL BE THE REMOVAL AND RELOCATION OF THE EXT'G STRUCTURE TO A NEW LOCATION TO THE EAST AND CONSTRUCTION OF A NEW RESIDENTIAL POOL. THE TOTAL SITE IS APPROXIMATELY 0.65 ACRES ACRES WITH THE ESTIMATED DISTURBED AREA TO BE 0.15 ACRES

2. DEVELOPER / CONTRACTOR : CABRETTA CAPITAL

BRENT WATTS
49 PARK OF COMMERCE WAY
SUITE 102
SAVANNAH, GEORGIA 31405

3. 24 HOUR CONTACT : BRENT WATTS 404-307-2868

4. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN CONFORMANCE WITH THE CURRENT STATE SOIL AND WATER CONSERVATION COMMITTEE OF GEORGIA "MANUAL FOR EROSION CONTROL IN GEORGIA.

5. PRIOR TO ANY OTHER CONSTRUCTION, STABILIZED CONSTRUCTION EXITS SHALL BE CONSTRUCTED AT EACH POINT OF ENTRY TO OR EXIT FROM THE SITE. ALL ENTRANCES TO THE SITE WHICH ARE NOT PROTECTED SHALL BE BARRICADED.

6. IMMEDIATELY AFTER THE ESTABLISHMENT OF CONSTRUCTION EXITS, ALL PERIMETER EROSION CONTROL DEVICES AND STORM WATER MANAGEMENT DEVICES SHALL BE INSTALLED PRIOR TO ANY OTHER CONSTRUCTION.

7. ADDITIONAL EROSION CONTROL DEVICES SHALL BE INSTALLED IMMEDIATELY AFTER GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE FINAL PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING ANY PHASE OF CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY!

8. THE LOCATIONS OF EROSION CONTROL DEVICES SHALL BE ADJUSTED AS CONSTRUCTION PROGRESSES IN ORDER TO MAINTAIN A FUNCTIONING EROSION CONTROL SYSTEM.

9. THE FAILURE OF ANY EROSION CONTROL DEVICE TO FUNCTION AS INTENDED, FOR ANY REASON, SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY!

10. EROSION CONTROL DEVICES SHALL BE INSPECTED AFTER EACH RAINFALL EVENT AND AT LEAST DAILY DURING PROLONGED PERIODS OF CONTINUOUS RAINFALLS.

11. EROSION CONTROL DEVICES SHALL BE CLEANED WHEN THEY BECOME HALF FILLED WITH SEDIMENT.

12. EROSION CONTROL DEVICES SHALL BE REPAIRED AS NECESSARY TO MAINTAIN A FUNCTIONING EROSION CONTROL SYSTEM.

13. EROSION CONTROL DEVICES SHALL BE MAINTAINED UNTIL PERMANENT COVER IS ESTABLISHED AND THEN REMOVED SO THAT DRAINAGE FROM THE SITE IS NOT IMPAIRED.

14. STORM WATER DETENTION DEVICES SHALL BE CLEANED AS SPECIFIED ABOVE AND AFTER PERMANENT GROUND COVER HAS BEEN ESTABLISHED.

15. ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH TEMPORARY SEEDING.

16. ANY DISTURBED AREAS WITH SLOPES 2:1 OR FLATTER WHICH ARE NOT STABILIZED

BY ANY OTHER MEASURES SHALL BE SEEDED AS SPECIFIED IN "PERMANENT SEEDING".

17. VEGETATIVE METHODS:

A VEGETATIVE COVER SHALL BE ESTABLISHED AND MAINTAINED OVER ALL FINAL GRADING AND OTHER DISTURBED AREAS OF THE SITE. SEE COASTAL PLAIN VEGETATIVE COVERS FOR AN OUTLINE OF THE ESTABLISHMENT OF VEGETATIVE COVERS.

WEEKLY INSPECTION OF THE GRASS COVER SHALL BE PERFORMED TO IDENTIFY AREAS REQUIRING RE-ESTABLISHMENT OF GRASS.

LIME RATE: 1 TO 2 TONS PER ACRE FERTILIZER: 1500 POUNDS OF 6-12-12 PER ACRE

18. MULCH

MULCH SHALL BE UNCHOPPED, UNROTTED, SMALL GRAIN DRY STRAW APPLIED AT A RATE OF 2 TONS PER ACRE. MULCH MATERIAL SHALL BE RELATIVELY FREE FROM ALL KINDS OF WEEDS AND SHALL BE FREE OF PROHIBITED NOXIOUS WEEDS WHICH ARE AS FOLLOWS: CANADA THISTLE, JOHNSONGRASS AND QUACKGRASS. SPREAD MULCH MECHANICALLY OR UNIFORMLY BY HAND. MULCH ANCHORING SHALL BE ACCOMPLISHED IMMEDPLACEMENTPIATELY AFTER MULCH PLACEMENT TO MINIMIZE LOSS BY WIND OR WATER. THIS MAY BE DONE BY PEG AND TWINE METHOD, MULCH ANCHORING TOOL, NETTING OR LIQUID MULCH BINDERS.

19. SOIL TYPE: THE SOILS IN THIS AREA HAVE BEEN CLASSIFIED BY THE SOIL CONSERVATION SERVICE AS BEING Cuc (Chipley-Urban Complex).

20. THIS DEVELOPMENT IS WITHIN FLOOD ZONE "AE-9" ACCORDING TO F.I.R.M. COMMUNITY PANEL NUMBER 13051CO - - , MAP REVISED - -.

21. THIS SITE IS IN ZONE "AE-9" AND IS LOCATED WITHIN THE 100 YEAR FLOOD ZONE.

SPECIAL NOTES:

1. THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTEDED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES.

2. THE INSTALLATION OF EROSION CONTROL MEASURES AND PRACTICES SHALL BE INSTALLED PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES.

3. EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES, IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

4. CITY OF TYBEE ISLAND PERSONNEL SHALL HAVE THE RIGHT TO INSPECT STORMWATER FACILITIES AT ALL TIMES.

5. STATE WATERS DO NOT EXIST WITHIN 200 FEET OF THE PROPERTY.

6. FRESH WATER WETLANDS DO NOT EXIST ON THIS PROPERTY.

7. THE EROSION AND SEDIMENT CONTROL PLAN DESIGNER HAS VISITED THE SITE PRIOR TO DESIGN OF THE E & SC PLANS.

8. THE RECEIVING WATERS FOR THIS PROJECT IS THE ADJACENT TYBEE ISLAND DRAINAGE SYSTEM, SALTWATER MARSH AND ULTIMATELY THE ATLANTIC OCEAN.

9. ANY DISTURBANCE AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABALIZED WITH TEMPORARY SEEDING.

10. AMENDMENTS OR REVISIONS TO THE ES & PC PLAN WHICH HAVE A HYDRAULIC EFFECT ON THE PROJECT MUST BE APPROVED BY THE DESIGN ENGINEER.

CLEARING NOTES:

1. ALL ELEVATIONS ARE BASED ON NAVD 88 DATUM.

2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL EXISTING UNDERGROUND UTILITIES PRIOR TO BEGINNING CONSTRUCTION ACTIVITIES AND FOR AVOIDING ALL CONFLICTS WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.

3. ALL WORK SHALL BE IN COMPLIANCE WITH THE STATE SOIL AND WATER CONSERVATION COMMITTEE'S "MANUAL FOR EROSION AND SEDIMENTATION CONTROL IN GEORGIA. ALL SEDIMENT CONTROL FEATURES SHALL BE MAINTAINED ON A REGULAR BASIS AND SHALL BE REMOVED BY THE CONTRACTOR UPON ACCEPTANCE OF THE SITE BY THE OWNER. SEE LAND DISTURBING PLAN.

4. ALL DISTURBED AREAS AND PROPOSED EARTH GRADING NOT TO BE COVERED BY OTHER SURFACES SHALL BE GRASSED AS DESCRIBED ON THE LAND DISTURBING ACTIVITY PLAN.

5. EGRESS FROM THE SITE WILL BE SUCH THAT ALL VEHICLES MUST TRAVERSE CONSTRUCTION EXITS TO REMOVE MUD FROM TIRES BEFORE ENTERING ANY PAVED PUBLIC HIGHWAY.

6. BALES OF HAY, STRAW OR SILT FENCE SHALL BE PLACED AROUND ALL STORM INLETS TO PREVENT SEDIMENT FROM ENTERING NEW PIPE OR DRAINAGE WAYS DURING CONSTRUCTION. THESE MEASURES ARE TEMPORARY.

7. THE SITE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING POSITIVE DRAINAGE OF ALL AREAS WITHIN THE PROJECT SITE INCLUDING RIGHTS—OF—WAYS, EASEMENTS AND LOTS. THE CONTRACTOR SHALL PROVIDE THE NECESSARY FILL AND OR GRADING TO MEET THE FINISHED PLAN GRADES AND ELIMINATE ANY AND ALL AREAS WHICH ARE LOW AND DO NOT DRAIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING PROPER DRAINAGE OF ANY AREAS WHICH ARE CHANGED AS A RESULT OF FIELD ADJUSTMENTS TO THE CONSTRUCTION PLANS.

8. THE CONTRACTOR WILL NOT BEGIN CLEARING OR ANY CONSTRUCTION ACTIVITY UNTIL THE APPROPRIATE PERMITS HAVE BEEN ISSUED.

9. IF REQUIRED, TREE PROTECTION BARRICADES SHALL BE INSTALLED PRIOR TO ANY CLEARING ACTIVITY AND MAINTAINED UNTIL INSTRUCTED BY OWNER OR ENGINEER

10. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO AVOID DAMAGE TO TREES AND ROOT SYSTEMS WHILE WORKING WITHIN TREE PROTECTION BARRICADES. THE CONTRACTOR SHALL NOT WORK WITHIN TREE PROTECTION BARRICADES WITHOUT A REPRESENTATIVE FROM THE OWNER OR ENGINEER PRESENT.

11. PRUNING OF TREE LIMBS, BRANCHES AND ROOTS OF TREES WHICH ARE WITHIN TREE PROTECTION BARRICADES SHALL BE DONE IN CONFORMANCE WITH SPECIFICATIONS AND RECOMMENDATIONS OF THE "NATIONAL ARBORIST ASSOCIATION" (N.A.A.) IN "PRUNING STANDARDS FOR SHADE TREES". ANY VARIATION FROM THE RECOMMENDATION OF THE N.A.A. SHALL BE APPROVED BY THE OWNER IN WRITING PRIOR TO ANY PRUNING.

12. LIMITS OF GRADING AND GRASSING ARE INDICATED ON PLANS AS "LIMITS OF DISTURBANCE".

13. ALL DISTURBED AREAS FROM NEW CONSTRUCTION ACTIVITIES WILL BE SEEDED, MULCHED, FERTILIZED AND WATERED TO PROMOTE A SUFFICIENT GROUND COVER THAT WILL PREVENT SOIL EROSION. SUFFICIENT COVERAGE SHALL BE AS SPECIFIED IN "EROSION CONTROL GRASSING".

14. DRAINAGE: ALL EXCAVATION SHALL BE PERFORMED SO THAT THE SITE AND THE AREA IMMEDIATELY SURROUNDING THE SITE WHICH EFFECTS THE OPERATIONS WILL BE CONTINUALLY AND EFFECTIVELY DRAINED. SURFACE WATER, GROUNDWATER, OR ANY PERCHED WATER WHICH MIGHT BE ENCOUNTERED DURING EXCAVATIONS SHALL BE REMOVED BY ANY ACCEPTABLE MEANS APPROVED BY THE ENGINEER.


TENTATIVE ACTIVITY SCHEDULE

		2024				
	SEP	ОСТ	NOV	DEC	JAN	FEB
INSTALLATION OF SEDIMENT CONTROLS AND TREE PROTECTION BARRICADES						
SITE GRADING						
UTILITY INSTALLATION		NO2	r API	PLICA	BLE	
BUILDING CONSTRUCTION						
PERMANENT GRASSING						
PAVING		NO	r API	PLICA	BLE	
MAINTENANCE OF SEDIMENT CONTROL						
REMOVAL OF SEDIMENT CONTROL						

SITE DATA

COASTAL PLAIN VEGETATIVE COVERS

MONTH OF PLANTING	TEMPORARY GRASS	RATE	MONTH OF PLANTING	PERMANENT GRASS	RATE
JANUARY— MARCH	ANNUAL LESPEDEZA	10 Lbs./Ac	MARCH- JUNE	CENTIPEDE SOD OR COMMON BERMUDA (HULLED)	10 Lbs./Ac
MARCH- JUNE	COMMON BERMUDA (HULLED)	10 Lbs./Ac	MARCH- JUNE	CENTIPEDE SOD OR COMMON BERMUDA (HULLED)	10 Lbs./Ac
APRIL- AUGUST	BROWN TOP MILLET	40 Lbs./Ac	JULY- AUGUST	COMMON BERMUDA (HULLED) OR CENTIPEDE SOD	10 Lbs./Ac
SEPTEMBER- FEBRUARY	RYEGRASS	40 Lbs./Ac	SEPTEMBER- FEBRUARY	COMMON BERMUDA (UNHULLED) OR CENTIPEDE SOD	10 Lbs./Ac 1/2 Bu./Ac



TEMPORARY CONSTRUCTION EXIT

LEVEL II CERTIFICATION NO. 2104 ISSUED 11-5-05 EXPIRES 11-5-23


EMA MAP NOTES:


. THIS DEVELOPMENT IS WITHIN FLOOD ZONE "AE-9" ACCORDING TO F.I.R.M.
COMMUNITY PANEL NUMBER 13051C-, MAP REVISED-(88 DATUM).


2. CONTRACTOR IS TO VERIPY FEMA ELEVATIONS PRIOR TO

Survey Information :
Survey : BREWER SURVEYING
Date of Survey : JULY, 2023
Datum : NAVD 88

Y CONSTRUCTION ACTIVITIES.







DRAWING NUMBER




6 OF 7 SHEETS

PRIOR TO DIGGING


Wail Bosine

No. 28372

PROFESSIONAL




UTILITY PLAN





ATER RESOURCES AND PUBLIC WORKS BUREAU


PLATE NUMBER:


WS4












CONSTRUCTION

DETAILS





INIMUM OF 1' ABOVE FLOOD.

ECIAL AE AND VE ZONE NOTES BUILDINGS IN "AE" ZONES ARE TO HAVE THE FINISHED FLOOR SET A

. BUILDINGS IN "VE" ZONES ARE TO HAVE THE LOWEST HORIZONTAL STRUCTURAL MEMBER SET A MINIMUM OF 1' ABOVE FLOOD.

. BUILDINGS IN AE AND VE ZONES ARE TO HAVE ALL ELECTRICAL, PLUMBING, VAC, DUCTWORK AND OTHER EQUIPMENT TO BE A MINIMUM OF 1' ABOVE

DETAILS

FLOOD VENTS ARE REQUIRED IN "AE" ZONES AND ARE TO HAVE I SQUARE INCH / SQUARE FOOT OF ENCLOSED AREA WITH A MINIMUM ROUND OPENING OF 3", A MINIMUM OF 2 OPENINGS WITH ALL OPENINGS EVENLY SPACED AROUND PERIMETER. BOTTOM OF OPENING SHALL BE 12" OR LESS ABOVE

. BREAK AWAY WALLS ARE REQUIRED IN "VE" ZONES.

. COORDINATE SITE WORK AND FINISHED FLOOR ELEVATIONS WITH RCHITECTURAL PLANS TO MAKE SURE BUILDING ELEVATIONS ARE SET AS PER

PLATE NUMBER:

1. THE OWNER, ENGINEER AND SURVEYOR ARE TO COORDINATE ALL EASEMENTS PRIOR TO FINAL PLAT APPROVAL AND

2. ALL DRAINAGE EASEMENTS TO BE PRIVATELY MAINTAINED.

TRAFFIC AND RIGHT-OF-WAY NOTES:

ALL ROAD CLOSINGS, DETOURS AND ETC. ARE TO BE COORDINATED WITH THE CITY OF TYBEE ISLAND, GEORGIA PERSONNEL.

2. ANY AND ALL NECESSARY PERMITS MUST BE OBTAINED FROM THE CITY OF TYBEE ISLAND PRIOR TO COMMENCEMENT OF ANY WORK WITHIN RIGHT-OF-WAY.

I. CONTRACTOR IS TO COORDINATE ALL GAS, LIGHTING, ELECTRICAL PHONE, CABLE AND ANY OTHER REQUIRED UTILITIES WITH THE APPROPRIATE UTILITY AGENCIES.

2. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO COMMENCING OF CONSTRUCTION ACTIVITIES AND FOR AVOIDING CONFLICT WITH SAME. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.

3. CONTRACTOR IS TO COORDINATE ALL DEMOLITION WORK WITH THE OWNER. ALL ITEMS NOT TO BE RELOCATED OR GIVEN TO THE OWNER WILL BECOME THE PROPERTY OF THE CONTRACTOR.

4. REMOVE ALL UNDERGROUND UTILITIES NOT TO BE UTILIZED. DO NOT ABANDON UTILITIES IN PLACE.

5. REMOVE ALL TREES AS NECESSARY FOR PROPOSED CONSTRUCTION.

6. PREVENT DAMAGE TO EXISTING TREES WHERE POSSIBLE.

X TREES TO BE REMOVED.

Special Pre-Construction Note:


Contractor to verify all existing and proposed structure locations (drainage, sanitary, etc.), tops and depths prior to ordering materials or beginning construction.


FEMA MAP NOTES : THIS DEVELOPMENT IS WITHIN FLOOD ZONE "AE-9" ACCORDING TO I.R.M. COMMUNITY PANEL NUMBER 13051C -, MAP REVISED --2. CONTRACTOR IS TO VERIFY FEMA ELEVATIONS PRIOR TO ANY CONSTRUCTION ACTIVITIES.


Survey Information: Survey: BREWER SURVEYIN Date of Survey : JULY, 202 Datum : NAVD 88

SPECIAL CONSTRUCTION NOTE:

IF THE CONTRACTOR KNOWS OR CAN REASONABLY BE EXPECTED TO HAVE KNOWN OF AN ERROR, DISCREPANCY OR CONFLICT IN THE PLANS, SPECIFICATIONS OR CONSTRUCTION STAKING AND FAILS TO REPORT THE PROBLEM PRIOR TO CONSTRUCTION, HE SHALL NOT BE ENTITLED TO COMPENSATION FOR ANY WORK OR EXPENSE INCURRED BY HIM FOR WORK REQUIRED TO BE RE-CONSTRUCTED BECAUSE OF SAID ERROR, DISCREPANCY OR CONFLICT.









Drawing Number